

한국에스지이에스(주) 건설시험연구원

성적서 번호 : G-24-0311-R0
진위확인용 랜덤번호 : SGS06WfMZq주소: 경기도 화성시 동탄산단 10길 20 및 동탄산단 10길 12
전화: 031-669-0600 팩스:031-646-0888
<https://www.sgsgroup.kr>

1. 의뢰인

- 기관명 : 한일시멘트(주)
- 주소 : 서울특별시 서초구 서초동 1587
- 의뢰일자 : 2023년 11월 20일

2. 시험성적서의 용도 : 품질관리 및 공급원승인용

3. 시험대상품목 또는 물질, 시료명 : FS 150(KS)

4. 시험기간 : 2023년 11월 20일 ~ 2024년 01월 05일

5. 시험장소 : 고정시험실 현장시험

(주소 : 경기도 화성시 동탄산단 10길 20 및 동탄산단 10길 12)

6. 시험결과 :

- 다음 페이지 참조 -

실무자 : 소 성 민
Tel : 031-669-0816기술책임자 : 엄 주 한
Tel : 031-646-0805

- ※비고 : 1. 이 시험성적서는 당초 의뢰자가 제출한 시료 및 시료명으로 시험한 결과로서 전체 제품에 대한 품질을 보증 하지는 않습니다.
2. 이 성적서는 홍보, 선전, 광고 및 소송용으로 사용될 수 없으며, 용도 이외의 사용을 금합니다.
3. 이 성적서의 원본 진위확인용은 한국에스지이에스 온라인 성적서 조회 홈페이지(<http://e-checking.kr.sgs.com/construction/>)에서 열람이 가능합니다.(랜덤 번호 기재 요)

2024년 01월 15일

한국에스지이에스(주) 건설시험연구원



페이지 1 / 2

This document is issued by the Company under its General Conditions of Service accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

CQP-708-001-F08 (02)

SGS Korea Co., Ltd. | 20, Dongtansandan 10-gil and 12, Dongtansandan 10-gil, Hwaseong-si, Gyeonggi-do, Korea, 18487 t +82(0)31 646 0800 f +82(0)31 646 0888 www.sgs.com

Member of SGS Group (Société Générale de Surveillance)

연 번	시 험 종 목		단 위	시 험 방 법	시 험 결 과
1	압축 강도	7 일	MPa	KS L 5220:2018	23.6
		28 일	MPa		41.2
2	보수성		%		69
3	공기량		vol%		8
4	모래의 함량(0.15 mm체 잔분)		%		69
5	모래의 최대크기	5.6 mm	%		100
		6.7 mm	%		100

※ 본 성적서는 KS Q ISO/IEC 17025 및 KOLAS 인정과 관련이 없습니다.

- 끝 -